

Approve purchase of splash pad

**VILLAGE OF WATERLOO
RESOLUTION NO. 08-13-19-05**

WHEREAS, the Village Board of Trustees have determined that the main park is in need of a splash pad; and

WHEREAS, the Park and Tree Board has presented a quote from Commercial Recreation Specialists (CRS) for the installation of a splash pad .


NOW THEREFORE, BE IT RESOLVED BY THE BOARD OF TRUSTEES OF THE VILLAGE OF WATERLOO, NEBRASKA, AS FOLLOWS:

THAT, the attached quote from CRS is hereby approved in the amount of ~~\$125,000~~ for purchase and installation of splash pad in the main park.
\$137,000 ~~##~~

PASSED THIS 13 **DAY OF** August, 2019

ATTEST:

Melissa Johnson
Melissa Johnson
Village Clerk



Village of Waterloo

Travis Harlow
Travis Harlow
Chairperson



COMMERCIAL RECREATION SPECIALISTS

August 23, 2019

Corie Sass
Melissa Johnson
Village of Waterloo
PO Box 127
Waterloo, NE 68069

RE: City Park Splashpad Design/Build Proposal
Turnkey Budget Design

The Commercial Recreation Specialists (CRS) Team is pleased to present this proposal, \$136,800.00 for a turnkey Splashpad Installation at City Park in Waterloo, NE. We are excited to share our many years of experience in the commercial recreation market to assist you in creating what we feel will be a very exciting and dynamic project.

Scope of Work Ref # SW20190823-JC1

Complete Product & Installation of a Commercial Splashpad to include the following:

- Installation of Vortex Water Features & Above Grade Cabinet Water Distribution System:
 - Includes Delivery of all Products as Noted on **Design 33731, Version A.**
 - Artist Renderings, Spray Zone Layout & Piping & Electrical Schematics.
- Installation and Concrete to Include:
 - Installation to be Performed by a Certified Vortex Installer.
 - Concrete Subbase to be 6" Compacted Class 5.
 - Concrete to be 6" thick, #4 Rebar Reinforced, 12" O.C., Medium Broom Finish.
 - Total Concrete Supplied: 1,900 sq. ft. (wet and dry zones combined) for Splashpad.
 - Grey Colored Concrete
 - Installation of Cabinet Manifold Command Center Near Pad, BFP, Pressure Regulator, Piping (to Include Schedule 80 PVC), Valves, Joints & Connections, Setting of Water Feature Foundations & Embeds & Installation of Vertical Water Features.
 - Backflow preventer (RPZ) to be installed by Licensed Plumber hired by CRS. Product included in Splashpad Equipment.
 - Electrical work to include power (120V) from subpanel supplied by owner near pad to Controller in Manifold Cabinet & Bonding of all Water Features and Concrete Rebar. CRS to hire local State Licensed Electrician. Includes Electrical Permit and Inspection prior to Concrete Pour.
 - Connect city provided water and storm sewer to splashpad Cabinet manifold & splashpad main drain.
 - Client to be Named as an Additional Insured.
 - Performance and Payment Bonds Included.





COMMERCIAL RECREATION SPECIALISTS

Startup & Training

- Perform initial startup of splashpad and train staff on recurring maintenance, winterization process, and pre-season startup.

Exclusions:

- Does Not Include City Provided Water Meter.
- City to provide potable water and storm sewer to pad. City to provide 120V power at subpanel near splashpad (building nearby).
- City to excavate splashpad area.
- Site to be Ready for Construction & Free of Debris or Obstructions.

Thank you for the opportunity to participate in this project. Please let us know if you have any questions on the above information. Thank you in advance for your consideration and we look forward to serving you and your team.

Sincerely,

Jeff Cornia
Sr. Account Manager
Commercial Recreation Specialists
Phone: 608-333-1654

